

-- 1 -- 67

JC13 RECEPTIFIED 2.5 MAR: 2002 CALL LABEL NO. EV004939544US

EDGG PATENT AND TRADEMARK OFFICE ATTORNEY'S DOCKET NUMBER

(REV 10-2000		IMENT OF COMMERCE PATENT AND TRADEMARK OFFICE	ATTORNETS DOCKET NOMBER							
TI	RANSMITTAL LETTER	REN-13087								
	DESIGNATED/ELECT	U.S. APPLICATION NO. (If known, see 37 CFR 1.5)								
	CONCERNING A FILI	NG UNDER 35 U.S.C. 371	10/089136							
INTERNA	ATIONAL APPLICATION NO.	INTERNATIONAL FILING DATE	PRIORITY DATE CLAIMED							
TITLE (	PCT/EP00/09569	29 September 2000	1 October 1999							
De		f Chemical Or Biological Reactions								
APPLICA W	ANT(S) FOR DO/EO/US olfgang Heimberg, Markus S	churf, Thomas Herrmann, Matthias Kr	nulle, Tilmann Wagner							
	t herewith submits to the United State	s Designated/Elected Office (DO/E O/US) the follo	wing items and other information:							
	This is a FIRST submission of item	s concerning a filing under 35 U.S.C. 371.	·							
2.	•	NT submission of items concerning a filing under 3								
3. <b>X</b>	This is an express request to prompt	ly begin national examination procedures (35 U.S.	C. 371(f)).							
4.	The US has been elected by the expir	ation of 19 months from the priority date (PCT A	rticle 31).							
5. <b>X</b>	A copy of the International App.	ication as filed (35 U.S.C. 371(c)(2))								
	, · · · ·	a. 🗵 is attached hereto (required only if not communicated by the International Bureau).								
		by the International Bureau.								
6. <b>X</b>	= '	oplication was filed in the United States Recei								
6. <b>X</b>		of the International Application as filed (35 Learnational Application under PCT Article	*							
النا ۱۰	<del></del>	aired only if not communicated by the International								
		ed by the International Bureau.	monar Bureau).							
	<del></del>	wever, the time limit for making such amendn	nents has NOT expired.							
	d. X have not been made and		•							
8.		of the amendments to the claims under PCT A	Article 19 (35 U.S.C. 371(c)(3)).							
9.	An oath or declaration of the inv		, , , , ,							
10.	An English language translation	of the annexes to the International Preliminary	Examination Report under							
	PCT Article 36 (35 U.S.C. 371(c)		-							
Items 1	1 to 16 below concern document	(s) or information included:								
11.	An Information Disclosure States	ment under 37 CFR 1.97 and 1.98.								
12.	An assignment document for reco	ording. A separate cover sheet in compliance	with 37 CFR 3.28 and 3.31 is included.							
13. 🕱	A FIRST preliminary amendmen									
	A SECOND or SUBSEQUENT p	reliminary amendment.								
14.	A substitute specification.									
15, 🔲	A change of power of attorney ar	d/or address letter.	·							
16.	Other items or information:									

JC13 Recid POT/BTO 25 MAR 2002

U.S. AFFEICATION N.D. (I	J/0897361°	VITERNATIONAL APPLICATION NO. PCT/EP00/0	9569		ATTORNEY'S DOG RE	N-13087	
17. <b>X</b> The fol	llowing fees are submitted:			C	ALCULATIONS		ľ
BASIC NATION	AL FEE (37 CFR 1.492 (a						
	national preliminary examin onal search fee (37 CFR 1.4						
	onal Search Report not prep		\$1000.00			4	
International USPTO but I	preliminary examination fee nternational Search Report p	e (37 CFR 1.482) not paid to prepared by the EPO or JPO	\$860.00				
International international	preliminary examination fee search fee (37 CFR 1.445(a	(37 CFR 1.482) not paid to USI (2)) paid to USPTO	PTO but <b>\$710.00</b>				
International	preliminary examination fee	e paid to USPTO (37 CFR 1.48 f PCT Article 33(1)-(4)	2) · · · · <b>\$690.00</b>				
International	preliminary examination fee	e paid to USPTO (37 CFR 1.48 Γ Article 33(1)-(4)	2)				
	ENTER APPROF	PRIATE BASIC FEE AM	IOUNT =	\$	890.00		
	0.00 for furnishing the oath earliest claimed priority dat		30	\$			
CLAIMS	NUMBER FILED	NUMBER EXTRA	RATE				
Total claims	32 - 20 =	12	X \$18.00	\$	216.00		
Independent claims	1 -3=	0	X \$80.00	\$	0.00		
MULTIPLE DEPE	ENDENT CLAIM(S) (if applica	ıble)	+ \$270.00	\$			
	TOTAL (	OF ABOVE CALCULAT	TIONS =	\$	1,106.00		
Applicant cl are reduced	aims small entity status. by 1/2.	See 37 CFR 1.27. The fees in	ndicated above	\$			
		SUBT	OTAL =	\$	553.00		
Processing fee of months from the	\$130.00 for furnishing the learliest claimed priority date	English translation later than	20	\$			
		TOTAL NATIONA	***	\$	553.00		
Fee for recording accompanied by a	the enclosed assignment (3) in appropriate cover sheet (3)	7 CFR 1.21(h)). The assignmer 37 CFR 3.28, 3.31). <b>\$40.00</b> per	nt mus t be	\$			
		TOTAL FEES ENCI	LOSED =	\$	553.00		
				Am	ount to be refunded:	\$	
					charged:	\$	
a. X A check	in the amount of $\frac{553}{}$	.00 to cover the above	e fees is enclosed				
h Dlagge of	oorgo my Donosit Assessat D	ar-					
A duplic	ate copy of this sheet is encl						S.
c. X The Con overpayr	nmissioner is hereby authori ment to Deposit Account No	zed to charge any additional fe b180160 A duplicate	es which may be copy of this she	requet is	nired, or credit a enclosed.	iny	
NOTE: Where 1.137(a) or (b))	an appropriate time limit must be filed and granted	under 37 CFR 1.494 or 1.495 to restore the application to	has not been m pendin g status.	iet, a	petition to rev	rive (37 CFR	
SEND ALL CORRESI	PONDENCE TO:						
Customer No				/"			_
Rankin, Hill,	Porter & Clark LLP		SIGNATUR				
700 Huntingt	<u> </u>		Kennet	h A	. Clark		_
925 Euclid A			NAME				
Cieveland, O	hio 44115-1405		32,119				- 1
							-
			REGISTRAT	I NOIT	NUMBER	APP No.	

# IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

#3/2

In re application of

Group Art Unit

Wolfgang Heimberg et al.

Examiner

Serial No.

Filed: March 25, 2002

Confirmation No.

For: DEVICE FOR THE CARRYING OUT OF

U.S. National Filing of PCT/EP00/09569

CHEMICAL OR BIOLOGICAL REACTIONS:

Filed 29 September 2000

Box PATENT APPLICATION Assistant Commissioner for Patents Washington, D.C. 20231

# PRELIMINARY AMENDMENT

Dear Sir:

Prior to calculating the filing fee and examining the above noted application, please proceed to amend the application as follows:

#### In the Claims:

Please cancel pending claims 1-18 without prejudice.

Please add new claims 19-50 as follows:

19. Device for the carrying out of chemical or biological reactions with a reaction vessel receiving element for receiving a microtiter plate with several reaction vessels, wherein the reaction vessel receiving element has several recesses arranged in a regular pattern to receive the respective reaction vessels, a heating device for heating the reaction vessel receiving element, and a cooling device for cooling the reaction vessel receiving element, wherein a) the reaction vessel receiving element is divided into several segments, b) each segment is assigned a heating device, wherein the

heating devices may be actuated independently of one another, c) the individual segments are thermally decoupled in such a way that different temperature levels may be set and maintained in two adjacent segments.

- 20. Device according to claim 19, wherein each segment of the reaction vessel receiving element is assigned a cooling device, wherein the cooling devices may be actuated independently of one another.
- 21. Device according to claim 19, wherein the segments of the reaction vessel receiving element are each comprised of a base plate with one or more tubular, thin-walled reaction vessel holders, which form one piece together with the base plate.
- 22. Device according to claim 20, wherein the segments of the reaction vessel receiving element are each comprised of a base plate with one or more tubular, thin-walled reaction vessel holders, which form one piece together with the base plate.
- 23. Device according to claim 19, wherein the individual segments are thermally decoupled by means of an air gap formed between adjacent segments.
- 24. Device according to claim 22, wherein the individual segments are thermally decoupled by means of an air gap formed between adjacent segments.
- 25. Device according to claim 19, wherein the individual segments are thermally decoupled by means of a gap, formed between adjacent segments, in which a thermal insulator is inserted.
- 26. Device according to claim 24, wherein the individual segments are thermally decoupled by means of a gap, formed between adjacent segments, in which a thermal insulator is inserted.

- 27. Device according to claim 19, wherein each of the heating devices has a Peltier element, wherein each case one segment of the reaction vessel receiving element is assigned a Peltier element, and the Peltier elements are thermally coupled to the respective segments.
- 28. Device according to claim 26, wherein each of the heating devices has a Peltier element, wherein in each case one segment of the reaction vessel receiving element is assigned a Peltier element, and the Peltier elements are thermally coupled to the respective segments.
- 29. Device according to claim 19, wherein the cooling devices comprise a Peltier element and/or a heat exchanger, wherein in each case one segment of the reaction vessel receiving element is assigned a Peltier element and/or a heat exchanger.
- 30. Device according to claim 29, wherein the cooling devices comprise a Peltier element and/or a heat exchanger, wherein in each case one segment of the reaction vessel receiving element is assigned a Peltier element and/or heat exchanger.
- 31. Device according to claim 29, wherein the heat exchanger is provided with cooling ducts through which a fluid may flow, wherein the fluidic flow of individual heat exchangers may be controlled independently of one another.
- 32. Device according to claim 30, wherein the heat exchanger is provided with cooling ducts through which a fluid may flow, wherein the fluidic flow of individual heat exchangers may be controlled independently of one another.
- 33. Device according to claim 31, wherein that the fluid is a cooling fluid, in particular water.
- 34. Device according to claim 32, wherein that the fluid is a cooling fluid, in particular water.

- 35. Device according to claim 19, wherein the reaction vessel receiving element is divided into at least four segments.
- 36. Device according to claim 34, wherein the reaction vessel receiving element is divided into at least four segments.
- 37. Device according to claim 19, wherein the individual segments each have the same number of recesses.
- 38. Device according to claim 36, wherein the individual segments each have the same number of recesses.
- 39. Device according to claim 19, wherein on their side edges the segments have downwards-facing hook elements by which they rest on ties.
- 40. Device according to claim 38, wherein on their side edges the segments have downwards-facing hook elements by which they rest on ties.
- 41. Device according to claim 19, wherein each segment is assigned a temperature sensor with which the temperature of the segment concerned is sensed, with the temperature of the segment being controlled on the basis of the temperatures sensed by the individual sensors.
- 42. Device according to claim 40, wherein each segment is assigned a temperature sensor with which the temperature of the segment concerned is sensed, with the temperature of the segment being controlled on the basis of the temperatures sensed by the individual sensors.
- 43. Device according to claim 19, wherein each segment is assigned one or more temperature equalisation elements.
- 44. Device according to claim 42, wherein each segment is assigned one or more temperature equalisation elements.

- 45. Device according to claim 19, wherein it has a control unit to actuate the heating device and the cooling device, wherein the control unit is so designed that the cooling devices of the individual segments may be actuated individually.
- 46. Device according to claim 44, wherein it has a control unit to actuate the heating device and the cooling device, wherein the control unit is so designed that the cooling devices of the individual segments may be actuated individually.
- 47. Device according to claim 45, wherein in one operating mode the control unit actuates only a part of the segments, wherein the segments have side edges, and the segments adjoining the side edges of an actuated segment are not actuated.
- 48. Device according to claim 46, wherein in one operating mode the control unit actuates only a part of the segments, wherein the segments have side edges, and the segments adjoining the side edges of an actuated segment are not actuated.
- 49. Device according to claim 45, wherein in one operating mode the segments are so actuated that the temperature difference between adjacent segments is less than a predetermined temperature difference ( $\Delta T$ ).

50. Device according to claim 48, wherein in one operating mode the segments are so actuated that the temperature difference between adjacent segments is less than a predetermined temperature difference ( $\Delta T$ ).

Respectfully submitted,

RANKIN, HILL, PORTER & CLARK LLP

Kenneth A. Clark Reg. No. 32,119

925 Euclid Avenue Suite 700 Cleveland, Ohio 44115-1405 (216) 566-9700

10\ren\13087\pa\2

ACA EFE E E E E E E E E

- EVUU47375440

JC13 Rec'd PCT/PTO 2 5 MAR 2002

10/089136

29/09/2000

5

10

25

30

PCT/EP 00/09569

# Device for the carrying out of chemical or biological reactions

The present invention relates to a device for the carrying out of chemical or biological reactions with

a reaction vessel receiving element for receiving reaction vessels, wherein the reaction vessel receiving element has several recesses arranged in a regular pattern to receive reaction vessels, a heating device for heating the reaction vessel receiving element, and a cooling device for cooling the reaction vessel receiving element.

- Such devices are described as thermocyclers or thermocycling devices and are 15 used to generate specific temperature cycles, i.e. to set predetermined temperatures in the reaction vessels and to maintain predetermined intervals of time.
- A device of this kind is known from US 5,525,300. This device has four reaction 20 vessel receiving elements, each with recesses arranged in a regular pattern. The pattern of the recesses corresponds to a known pattern of reaction vessels of standard microtiter plates, so that microtiter plates with their reaction vessels may be inserted in the recesses.

The heating and cooling devices of a reaction vessel receiving element are so designed that a temperature gradient extending over the reaction vessel receiving element may be generated. This means that, during a temperature cycle, different temperatures may be obtained in the individual reaction vessels.

This makes it possible to carry out certain experiments at different temperatures simultaneously.

5

10

15

30

This temperature gradient is used to determine the optimal denaturing temperature, the optimal annealing temperature and the optimal elongation temperature of a PCR reaction. To achieve this, the same reaction mixture is poured into the individual reaction vessels, and the temperature cycles necessary to perform the PCR reaction are executed. Such a temperature cycle comprises the heating of the reaction mixture to the denaturing temperature, which usually lies in the range 90°-95°C, cooling to the annealing temperature, which is usually in the range 40°-60°C, and heating to the elongation temperature, which is usually in the range 70-75°C. A cycle of this kind is repeated several times, leading to amplification of a predetermined DNA sequence.

Since a temperature gradient can be set, different but predetermined temperatures are set in the individual reaction vessels. After completion of the cycles it is possible to determine, with the aid of the reaction products, those temperatures at which the PCR reaction will give the user the optimal result. Here the result may be optimised e.g. in respect of product volume or also product quality.

The annealing temperature, at which the primer is added, has a powerful influence on the result. However the elongation temperature too can have beneficial or adverse effects on the result. At a higher elongation temperature, the addition of the bases is accelerated, with the probability of errors increasing with higher temperature. In addition, the life of the polymerase is shorter at a higher elongation temperature.

A thermocycling device, by which the temperature gradient may be set, makes it much easier to determine the desired temperatures, since a reaction mixture my simultaneously undergo cycles at different temperatures in a single thermocycling device.

5

10

15

20

25

30

3

Another important parameter for the success of a PCR reaction is the residence time at the individual temperatures for denaturing, annealing and elongation, and the rate of temperature change. With the known device, these parameters can not be varied in one test series for an individual reaction vessel holder. If it is desired to test different residence times and rates of change, this can be done in several test series either consecutively on one thermocycling device or simultaneously in several thermocycling devices.

For this purpose there are so-called multiblock thermocycling devices with several reaction vessel receiving elements, each provided with separate cooling, heating and control devices (see US 5,525,300). The reaction mixture to be tested must be distributed over several microtiter plates, for testing independently of one another.

To determine the optimal residence times and rates of temperature change it is necessary to have either several thermocycling devices or a multiblock thermocycling device, or to carry out tests in several consecutive test series. The acquisition of several thermocycling devices or of a multiblock thermocycling device is costly and the carrying-out of several consecutive test series takes too long. In addition, handling is laborious when only part of the reaction vessels of several microtiter plates is filled, with each of the latter being tested and optimised in separate test series. This is especially disadvantageous in the case of device which operate automatically and in which the reaction mixtures are subject to further operations, since several microtiter plates must then be handled separately. It is also extremely impractical when only part of the reaction vessels of the microtiter plates is filled, since the devices for further processing, such as e.g. sample combs for transferring the reaction products to an electrophoresis apparatus, are often laid out on the grid of the microtiter plates, which means that further processing is correspondingly limited if only part of the reaction vessels of the microtiter plate is used.

5

10

15

20

25

4

US 5,819842 discloses a device for the individual, controlled heating of several samples. This device has several flat heating elements arranged in a grid pattern on a work surface. Formed below the heating elements is a cooling device which extends over all the heating elements. In operation a specially designed sample plate is placed on the work surface. This sample plate has a grid plate, covered on the underside by a film. The samples are poured into the recesses of the grid plate. In this device the samples lie on the individual heating elements, separated from them only by the film. By this means, direct heat transfer is obtained. The drawback of this device, however, is that no commonly available microtiter plate can be used.

With increasing automation in biotechnology, thermocyclers are increasingly being used in automated production lines and with robots as one of several work stations. Here it is customary for the samples to be passed in microtiter plates from one work station to the next. If the device according to US 5,819,842 were to be used in such an automated production process, it would be necessary for the samples to be pipetted out of a microtiter plate into the specially designed sample plate before temperature adjustment, and from the sample plate into a microtiter plate after temperature adjustment. Here there is a risk of contamination of the samples. The use of this specially designed sample plate must therefore be regarded as extremely disadvantageous.

The invention is based on the problem of developing the device described above in such a way that the disadvantages described above are avoided and the parameters of the PCR process may be optimised with great flexibility.

To solve this problem the invention has the features specified in claim1.

Advantageous developments thereof are set out in the additional claims.

The invention is characterised by the fact that the reaction vessel receiving element is divided into several segments, with the individual segments thermally

5

decoupled and each segment assigned a heating device which may be actuated independently.

By this means the individual segments of the device may be set to different temperatures independently of one another. This makes it possible not only to set different temperature levels in the segments, but also for them to be held for varying lengths of time or altered at different rates of change. The device according to the invention thus permits optimisation of all physical parameters critical for a PCR process, while the optimisation process may be carried out on a single reaction vessel receiving element in which a microtiter plate may be inserted.

With the device according to the invention it is therefore also possible to optimise the residence times and rates of temperature change without having to distribute the reaction mixture over different microtiter plates for this purpose.

The thermocycling device according to the invention is in particular suitable for optimising the multiplex PCR process, in which several different primers are used.

20

15

5

10

The above problem, and the features and advantages according to the present invention, may be better understood from the following detailed description of preferred embodiments of the present invention and with reference to the associated drawings.

25

The invention is explained in detail below with the aid of the drawings. These show in:

Fig. 1 a section through a device according to the invention for carrying out chemical or biological reactions in accordance with a first embodiment,

30

6

	Fig. 2	a section through an area of a device according to the invention for carrying out chemical or biological reactions in accordance with a second embodiment,
5	Fig. 3	a schematic plan view of the device of Fig. 2,
	Fig. 4	a schematic plan view of a device according to a third embodiment
10	Fig. 5	an area of the device of Fig. 4 in a sectional view along the line A-A,
4 -	Figs. 6 to 9	schematic plan views of reaction vessel receiving elements with differing segmentation
15	Fig. 10	a clamping frame in plan view
20	Fig. 11	a device according to the invention in which segments of a reaction vessel receiving element are fixed by the clamping frame according to Fig. 10, and
0.5	Fig. 12	a further embodiment of a device according to the invention in section, in which segments of a reaction vessel receiving element are fixed by the clamping frame according to Fig. 10.
25	•	s a first embodiment of the device 1 according to the invention for chemical or biological reactions in a schematic sectional view.

The device has a housing 2 with a bottom 3 and side walls 4. Located just above

and parallel to the bottom 3 is an intermediate wall 5, on which are formed

5

10

15

20

25

7

several bases 5a. In the embodiment shown in Fig. 1, a total of six bases 5a are provided, arranged in two rows of three bases 5a each.

Mounted on each of the bases 5a is a heat exchanger 6, a Peltier element 7 and a segment 8 of a reaction vessel receiving element 9. The heat exchanger 6 is part of a cooling device and the Peltier element 7 is part of a combined heating and cooling device. The elements (heat exchanger, Peltier element, segment) mounted on the bases 5a are bonded by an adhesive resin with good heat conducting properties, so that good heat transfer is realised between these elements, and the elements are also firmly connected to a segment element 10. the device has altogether six such segment elements 10. Instead of adhesive resin, a heat conducting film or a heat conducting paste may also be provided.

Each of the segments 8 of the reaction vessel receiving element 9 has a base plate 11 on which tubular, thin-walled reaction vessel holders 12 are integrally formed. In the embodiment depicted in Fig. 1, in each case 4 x 4 reaction vessel holders 12 are arranged on a base plate 11. The distance d between adjacent segments 8 is such that the reaction vessel holders 12 of all segments 8 are arranged in a regular pattern with constant grid spacing D. The grid spacing D is chosen so that s standardised microtiter plate with its reaction vessels may be inserted in the reaction vessel holders 12.

By providing the distance d between adjacent segments, an air gap which thermally decouples the segments 8 and segment elements 10 respectively is formed.

The reaction vessel holders 12 of the device shown in Fig. 1 form a grid with a total pf 96 reaction vessel holders, arranged in eight rows each with twelve reaction vessel holders 12.

5

10

15

25

30

8

The Peltier elements 7 are each connected electrically to a first control unit 13. Each of the heat exchangers 6 is connected via a separate cooling circuit 14 to a second control unit 15. The cooling medium used is for example water, which is cooled in the cool temperature control unit before transfer to one of the heat exchangers 6.

The first control unit 13 and the second control unit 15 are connected to a central control unit 16 which controls the temperature cycles to be implemented in the device. Inserted in each cooling circuit 14 is a control valve 19, which is controlled by the central control unit 16 to open or close the respective cooling circuit 14.

Pivotably attached to the housing 2 is a cover 17 in which additional heating elements 18 in the form of Peltier elements, heating films or semiconductor heating elements may be located. The heating elements 18 form cover heating elements, each assigned to a segment 8 and separately connected to the first control unit 13, so that each heating element 18 may be individually actuated.

The mode of operation of the device according to the invention is explained in detail below.

There are three modes of operation.

In the first operating mode all segments are set to the same temperature, i.e. the same temperature cycles are run on all segments. This operating mode corresponds to the operation of a conventional thermocycling device.

In the second operating mode the segments are actuated with different temperatures, wherein the temperatures are so controlled that the temperature difference  $\Delta T$  of adjacent segments 8 is less than a predetermined value K which amounts for example to  $5^{\circ}$ -15°C. The value to be chosen for K depends on the

5

10

25

30

9

quality of the thermal decoupling. The better the thermal decoupling, the greater the value which can be chosen for K.

The temperature cycles input by the user may be distributed automatically by the central control unit 16 to the segments 8, so that the temperature differences between adjacent segments are kept as small as possible.

This second operating mode may be provided with a function by which the user inputs only a single temperature cycle or PCR cycle, and the central control unit 16 then varies this cycle automatically. The parameters to be varied, such as temperature, residence time or rate of temperature change, may be chosen by the user separately or in combination. Variation of the parameters is effected either by linear or sigmoidal distribution.

In the third operating mode, only part of the segments is actuated. In plan view (Fig. 3, Fig. 4, Figs. 6 to 9) the segments 8 have side edges 20. In this operating mode, the segments 8 adjacent to the side edges of an actuated segment 8 are not actuated. If the segments 8 themselves form a regular pattern (Fig. 3, Fig. 4, Fig. 6, Fig. 7 and Fig. 8), then the actuated segments are distributed in a chessboard pattern. In the embodiments shown in Figs. 1 to 4, three of the six segments 8 can be actuated, namely the two outer segments of one row and the middle segment of the other row.

In this operating mode the actuated segments are not influenced by the other segments, and their temperature may be set completely independently of the other actuated segments. By this means it is possible to run quite different temperature cycles on the individual segments, with one of the segments for example heated up to the denaturing temperature and another held at the annealing temperature. Thus it is possible for the residence times, i.e. the intervals of time for which the denaturing temperature, the annealing temperature and the elongation temperature are held, also the rates of temperature change,

10

to be set as desired, and run simultaneously on the individual segments. In this way it is possible to optimise not only the temperatures, but also the residence times and the rates of temperature change.

In this operating mode it may be expedient to heat the non-actuated segments 8 a little, so that their temperature lies roughly in the range of the lowest temperature of the adjacent actuated segments. This avoids the non-actuated segments forming a heat sink for the actuated segments and affecting their temperature profile adversely.

10

30

A second embodiment of the device according to the invention is shown in Figs. 2 and 3. the basic design corresponds to that of Fig. 1, so that identical parts have been given the same reference number.

15 The second embodiment differs from the first embodiment by virtue of the fact that the side edges 20 of the segments 8 adjacent to the side walls 4 of the housing 2 engage in a slot 21 running round the inner face of the side walls 4, and are fixed therein for example by bonding. By this means the individual segment elements 10 are fixed in space, thereby ensuring that despite the form of the gaps between the segment elements 10, all reaction vessel holders 12 are arranged in the pattern of the reaction vessels of a microtiter plate. The side walls 4 of the housing 2 are made of a non heat conducting material. This embodiment may also be modified such that the slot 21 is introduced in a frame formed separately from the housing 2. The frame and the segments inserted in it form a part which may be handled separately during production and is bonded to the heating and cooling devices.

A third embodiment is shown schematically in Figs. 4 and 5. In this embodiment, ties 22 of non heat conducting material are located somewhat below the base plates 11 of the segments 8 in the areas between the segment elements 10 and between the segment elements 10 and the side walls 4 of the housing 2. On the

5

10

15

11

side edges 20 of the segments 8 and of the base plates 11 respectively are formed hook elements 23 which are bent downwards. These hook elements 23 engage in corresponding recesses of the ties 22 (Fig. 5), thereby fixing the segments 8 in their position. The hook elements 23 of adjacent segments 8 are offset relative to one another. The ties 22 thus form a grid, into eeach of the openings of which a segment 8 may be inserted.

This type of position fixing is very advantageous since the boundary areas between the segments 8 and the ties 22 are very small, so that heat transfer via the ties 22 is correspondingly low. Moreover this arrangement is easy to realise even in the confined space conditions between adjacent segment elements.

Shown in schematic plan view in Figs. 6 to 9 are reaction vessel receiving elements 9 which represent further modifications of the device according to the invention. In these reaction vessel receiving elements 9, the individual segments 8 are joined by webs 24 of a thermally insulating material joined to form a single unit The ties 22 are arranged between the side edges 20 of the base plates 11, to which they are fixed for example by bonding.

The segmentation of the reaction vessel receiving element of Fig. 6 corresponds to that of the first and second embodiment (Fig. 1-3), in which 4 x 4 reaction vessel holders are arranged on each segment 8.

The reaction vessel receiving element 9 shown in Fig. 7 is comprised of 24 segments 8 each with 4 x 4 reaction vessel holders 12, while the segments 8 are in turn connected by means of thermally insulating webs 24.

In the reaction vessel receiving element 9 shown in Fig. 8, each segment 8 has only a single reaction vessel holder 12.

12

For the relatively finely sub-divided reaction vessel receiving elements 9 it is expedient to integrate temperature sensors in the thermocycling device. These temperature sensors sense the temperatures of the individual segments, so that the temperature of the segments 8 is regulated in a closed control loop on the basis of the temperature values determined by the temperature sensors.

Infrared sensors may for example be used as temperature sensors, located e.g. in the cover. With this sensor arrangement it is possible to sense the temperature of the reaction mixture directly.

10

15

5

Fig. 9 shows a reaction vessel receiving element 9 with six segments 8, rectangular in plan view, and a segment 8a in the form of a double cross formed by three intersecting rows of reaction vessel holders 12. The six rectangular segments 8 are each separated from the next rectangular segment by a row or column of reaction vessel holders. This segmentation is especially advantageous for the third operating mode described above, since the rectangular segments 8 are not in contact with one another and may therefore be actuated simultaneously as desired, with only the segment 8a in the form of a double cross not being actuated.

20

The segments 8 of the reaction vessel receiving element 9 are made from a metal with good heat conducting properties, e.g. aluminium. The materials described above as non-heat conducting materials or thermally insulating materials are either plastics or ceramics.

25

A further embodiment of the device according to the invention is shown in Fig. 11. In this embodiment the individual segments 8b of the reaction vessel receiving element 9 are fixed in position by means of a clamping frame 25 (Fig. 10).

5

10

15

20

25

30

The clamping frame 25 is grid-shaped and formed by longitudinal ties 26 and cross ties, wherein the ties 26, 27 span openings. Through these openings extend the reaction vessel holders 12 of the segments 8b. In the present embodiment, the ties 26, 27 are for instance in positive contact with the reaction vessel holders 12 and with the base plate 11 which protrudes from the reaction vessel holders. The 25 is provided with holes 28, through which pass bolts 29 for fixing the clamping frame to a thermocycling device 1.

Located below each of the segments 8b is a separately actuable Peltier element 7 and a cooling element 30 which extends over the area of all the segments 8b. Located in each case between the cooling element 30 and the Peltier element 7, and between the Peltier element 7 and the respective segment 8b is a heat conducting foil 31. The cooling element 30 is provided with holes through which extend the bolts 29, each fixed by a nut 32 to the side of the cooling element 30 facing away from the reaction vessel receiving element 9.

The clamping frame 25 is made from a non heat conducting material, in particular POM or polycarbonate. It therefore allows a fixing of the segments 8b of the reaction vessel receiving element 9 wherein the individual elements between the segments 8b and the cooling element 30 are under tension, thereby ensuring good heat transfer in the vertical direction between the individual elements. Since the clamping frame itself has poor heat conducting properties, the heat transfer between two adjacent segments 8b is kept low. For further reduction of heat transfer between two adjacent segments, the surfaces of the clamping frame 25 in contact with the segments 8b may be provided with narrow webs, so that in the areas adjoining the webs, air gaps are formed between the clamping frame 25 and the segments 8b.

In the embodiment shown in Fig. 11, a so-called heat pipe 33 is fitted between every two rows of reaction vessel holders 12. Such a heat pipe is distributed for example by the company THERMACORE INTERNATIONAL, Inc., USA. It is

14

comprised of a gastight jacket, in which there is only a small amount of fluid. The pressure in the heat pipe is so low that the fluid is in a state of equilibrium between the liquid and the gaseous aggregate state, and consequently evaporates at a warmer section of the heat pipe and condenses at a cooler section. By this means, the temperature between the individual sections is equalised. The fluid used is, for example, water or freon.

Through integration of such a heat pipe in the segments 8b of the reaction vessel receiving element 9, a temperature equalisation is effected over the segment 8b. By this means it is ensured that the same temperature is present over the whole segment 8b.

A further embodiment of the thermocycling device 1 according to the invention is shown in Fig. 12. The design of this thermocycling device 1 is similar to that of Fig. 11, therefore similar parts have been given the same reference numbers.

The segments 8c of this thermocycling device 1, however, have no heat pipe. Instead of heat pipes, a temperature equalisation plate 34 is provided in the area beneath each of the segments 8c. These temperature equalisation plates 34 are flat elements with a surface corresponding to the basic surface of one of the segments 8c. These temperature equalisation plates 34 are hollow bodies with a small amount of fluid, and work on the same principle as the heat pipes. By this means it is once again ensured that there are no temperature variations within a segment 8c.

25

30

20

5

10

15

The temperature equalisation plate may however be made from materials with very good heat conducting properties, such as e.g. copper. Additional heating and/or cooling elements, e.g. heating foils, heating coils or Peltier elements, may be integrated in such a temperature equalisation plate. The heating and cooling elements support homogeneity and permit more rapid heating and/or cooling

15

rates. A Peltier element, which generally does not have an even temperature distribution, is preferably combined with a flat heating element.

The invention is described above with the aid of embodiments with 96 recesses for receiving a microtiter plate with 96 reaction vessels. The invention is not however limited to this number of recesses. Thus for example the reaction vessel receiving element may also have 384 recesses to receive a corresponding microtiter plate. With regard to features of the invention not explained in detail above, express reference is made to the claims and the drawing.

10

5

In the embodiments described above, a cooling device with a fluid cooling medium is used. Within the scope of the invention it is also possible to use a gaseous cooling medium, in particular air cooling, instead of a fluid cooling medium.

15

The reaction vessel receiving elements described above are comprised of a base plate with roughly tubular reaction vessel holders. Within the scope of the invention it is also possible to use a metal block, in which recesses to receive the reaction vessels of the microtiter plate are made.

16

# List of References

	1	thermocycling device	25	clamping frame
	2	housing	26	longitudinal tie
5	3	bottom	27	cross tie
	4	side wall	28	hole
	5	intermediate wall	29	bolt
	5a	base	30	cooling element
	6	heat exchanger	31	heat conducting foil
10	7	Peltier element	32	nut
	8	segment	33	heat pipe
	8a	segment in the form of a	34	temperature equalisation plate
		double cross		
	9	reaction vessel receiving element	t	
15	10	segment element		
	11	base plate		
	12	reaction vessel holder		
	13	first control unit		
	14	cooling circuit		
20	15	second control unit		
	16	central control unit		
	17	cover		
	18	heating element		
	19	control valve		
25	20	side edge		
	21	slot		
	22	ties		
	23	hook element		
	24	web		

### Patent Claims

- Device for the carrying out of chemical or biological reactions with
   a reaction vessel receiving element (9) for receiving a microtiter plate with
   several reaction vessels, wherein the reaction vessel receiving element (9) has
   several recesses arranged in a regular pattern to receive the respective reaction
   vessels,
- a heating device (7) for heating the reaction vessel receiving element (9), and a cooling device (6) for cooling the reaction vessel receiving element (9), characterised in that the reaction vessel receiving element (9) is divided into several segments (8), with the individual segments (8) thermally decoupled and each segment (8) assigned a heating device (7) which may be actuated independently of the others.
- Device according to claim 1,
   characterised in that
   each segment (8) of the reaction vessel receiving element (9) is assigned a
   cooling device (6), wherein the cooling devices (6) may be actuated independently of one another.
  - 3. Device according to claim 1 or 2, characterised in that the segments (8) of the reaction vessel receiving element (9) are each comprised of a base plate (11) with one or more tubular, thin-walled reaction vessel holders (12), which form one piece together with the base plate (11).
    - 4. Device according to any of claims 1 to 3,
- 30 characterised in that

18

the individual segments (8) are thermally decoupled by means of an air gap formed between adjacent segments (8).

- 5. Device according to any of claims 1 to 3,
- 5 characterised in that the individual segments (8) are thermally decoupled by means of a gap, formed between adjacent segments (8), in which a thermal insulator is inserted.
  - 6. Device according to any of claims 1 to 5,
- characterised in that
  each of the heating devices has a Peltier element (7), wherein in each case one
  segment (8) of the reaction vessel receiving element (9) is assigned a Peltier
  element (7), and the Peltier elements (7) are thermally coupled to the respective
  segments (8).

15

20

25

- 7. Device according to any of claims 1 to 6, characterised in that the cooling devices comprise a Peltier element (7) and/or a heat exchanger (6), wherein in each case one segment (8) of the reaction vessel receiving element (9) is assigned a Peltier element (7) and/or a heat exchanger (6).
- 8. Device according to claim 7, characterised in that the heat exchanger (6) is provided with cooling ducts through which a fluid may flow, wherein the fluidic flow of individual heat exchangers (6) may be controlled independently of one another.
- Device according to claim 8,
   characterised in that
   that the fluid is a cooling fluid, in particular water.

19

10. Device according to any of claims 1 to 9,characterised in thatthe reaction vessel receiving element (9) is divided into at least four segments (8).

- 11. Device according to any of claims 1 to 10,characterised in thatthe individual segments (8) each have the same number of recesses.
- 10 12. Device according to any of the preceding claims, characterised in that on their side edges (20) the segments (8) have downwards-facing hook elements (23) by which they rest on ties 22.
- 15 13. Device according to any of claims 1 to 12, characterised in that each segment (8) is assigned a temperature sensor with which the temperature of the segment (8) concerned is sensed, with the temperature of the segment (8) being controlled on the basis of the temperatures sensed by the individual sensors.
- 14. Device according to any of claims 1 to 13,
  characterised in that
  each segment (8b, 8c) is assigned one or more temperature equalisation
  elements (33, 34).
  - 15. Control unit to actuate the heating device and the cooling device of a device for the carrying out of chemical or biological reactions, which is designed according to any of claims 1 to 14,
- 30 characterised in that

20

the control unit (13, 16) is so designed that the heating devices (7) of the individual segments (8) may be actuated individually.

- 16. Control unit according to claim 15,
- 5 characterised in that the control unit (15, 16) is so designed that the cooling devices of the individual segments (8) may be actuated individually.
  - 17. Control unit according to claim 15 or 16,
- 10 characterised in that in one operating mode the control unit (13, 15, 16) actuates only a part of the segments, wherein the segments (8) have side edges (20), and the segments (8) adjoining the side edges (20) of an actuated segment (8) are not actuated.
- 15 18. Control unit according to any of claims 15 to 17, characterised in that in one operating mode the segments are so actuated that the temperature difference between adjacent segments (8) is less than a predetermined temperature difference (ΔT).

21

## Summary

The invention relates to a device for the carrying out of chemical or biological reactions with a reaction vessel receiving element for receiving a microtiter plate with several reaction vessels, wherein the reaction vessel receiving element has several recesses arranged in a regular pattern to receive the respective reaction vessels, a heating device for heating the reaction vessel receiving element, and a cooling device for cooling the reaction vessel receiving element.

10

5


The invention is characterised by the fact that the reaction vessel receiving element is divided into several segments. The individual segments are thermally decoupled from one another, and each segment is assigned a heating device which may be actuated independently of the others.


15


20


By means of the segmentation of the reaction vessel receiving element, it is possible for zones to be set and held at different temperatures. Since the reaction vessel receiving element is suitable for receiving standard microtiter plates, the device according to the invention may be integrated in existing process sequences.


(Fig. 1)































supplemental priority data sheet PTO/SB/02B attached hereto.

Please type a plus sign (+) inside this box  Under the Paperwork Reduction Act of 1995, no per		U.S. Patent a	nd Trademark Offic	PTO/SB/01 (10-00) use through 10/31/2002, OMB 0651-0032 ce; U.S. DEPARTMENT OF COMMERCE is it contains a valid OMB control number,
		Attorney Docke	et Number	REN-13087
DECLARATION FOR UTIL DESIGN	ITY OR	First Named In	ventor	Wolfgang Heimberg
PATENT APPLICATION	ON ·	cc	MPLETE IF K	NOWN
(37 CFR 1.63)		Application Nur	nber	10 / 089136
		Filing Date		25 March 2002
	ation ited after Initial surcharge	Group Art Unit		
with Initial Filing (37 CF require	R 1.16 (e))	Examiner Name	e	
names are listed below) of the subject mate  Device For The Ca  the specification of which	rrying Out Of (			
is attached hereto OR  was filed on (MM/DD/YYYY)  Application Number  10/089136  I hereby state that I have reviewed and un amended by any amendment specifically of acknowledge the duty to disclose informatin-part applications, material information we PCT international filing date of the continue.	derstand the cont elerred to above. tion which is mat hich became ava	ended on (MM/DD/YY ents of the above ide erial to patentability a ilable between the fili	YY)	CFR 1.56 including for continuation-
I hereby claim foreign priority benefits und certificate, or 365(a) of any PCT international America, listed below and have also idecertificate, or any PCT international applications.	ler 35 U.S.C. 119 onal application w	P(a)-(d) or 365(b) of a high designated at le	ast one country any foreign app	other than the United States of lication for patent or inventor's
Prior Foreign Application	Country	Foreign Filing Date (MM/DD/YYYY)		Certified Copy Attached? YES NO
	ermany Europe	10/01/1999 09/29/2000	0000	
☐ Additional foreign application numbers	are listed on a se	upplemental priority d	ata sheet PTO/S	B/02B attached hereto:
I hereby claim the benefit under 35 U.S.	C. 119(e) of any l	United States provisio	nal application(s	) listed below.
Application Number(s)	Filing Date (	(MM/DD/YYYY)		inal provisional application irs are listed on a

[Page 1 of 2]
Burden Hour Statement: This form is estimated to take 21 minutes to complete. Time will vary depending upon the needs of the individual case. Any comments on the amount of time, you are required to complete this form should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, Washington, DC 20231. DO NOT SEND FEES OR COMPLETED, FORMS TO THIS ADDRESS, SEND TO: Assistant Commissioner for Patents, Washington, DC 20231.

PTO/SB/01 (10-00)

Approved for use through 10/31/2002. OMB 0651-0032

U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

DECLARATION —	Utility or De	esign Patent /	Application
Direct all correspondence to:   Customer No or Bar Code		09) OR [] C	omespondence address below
Name Rankin, Hill, Porter & Cla	rk LLP	-	
Address 925 Euclid Avenue, Suite	700		
Address			
city Cleveland		State Ohio	ZIP 44115-1405
Country U.S.A.	Telephone (216)	566-9700	Fax (216) 566-9711
I hereby declare that all statements made herein of are believed to be true; and further that these stat made are punishable by fine or imprisonment; or be validity of the application or any patent issued there	ements were made wil	the knowledges that willful	false of a demands and the like se
NAME OF SOLE OR FIRST INVENTOR :		A petition has been	া সভ unsigned inventor
Given Name (first and middle [if any]) Wolfga	ing	Family Name or Surname	Heimberg
Inventor's X QO	e(20mg	Ty	Date 31.10.2002
Residence: City Ebersberg	DEX State	Country DE	Citizenship German
Mailing Address Bohmerwaldstr. 72			
Mailing Address			. 3
City Ebersberg State		ZIP 85560	Country Germany
NAME OF SECOND INVENTOR:		A petition has been **	ais unsigned inventor
Given Name (first and middle [if any])  Thom	u.,,	Family Name or Surname	Herrmann
Inventor's X Thomas	es Hem		Date 31.10,2002
Residence: City Ottobrunn	DEX State	Country DE	Citizenship German
Mailing Address Putzbrunner Strasse 40a			
Mailing Address			
City Ottobrunn State		ZIP 85521	Country Germany
Additional inventors are being named on the 1		al Inventor(s) sheet(s) PTO/	

PTO/SB/02A (3-97)
sign (+) inside this box — 

Approved for use through 9/30/98. OMB 0551-0032
Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE
Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number.

# **DECLARATION**

# ADDITIONAL INVENTOR(S) Supplemental Sheet

nal Joint Inventor, if any	<b>7</b> 5	[		petitlo	n has	- this	s unsigi	ned inv	ventor
me (first and middle [if any])					Family Na::	ie or Su	ımame		
<u>Matthias</u>	1				<u>K</u>	nulle			
X M.	us,	ll					Date	)	18.M. 2002
Grafing	State	DEK	ء ا	ountry	Germany		Citizons	hip	German
Dietrich Bonhocff	er Stra	issc 4							
Grafing	State			ZIP	85567		Ge	rman	у
nal Joint Inventor, if any	<u>/</u>			A petitio	n has 🗽	45	s unsig	ned in	ventor
me (first and middle (if any)	)				Formily Nan	e or Su	ırname		
Markus		<i>-11</i>			•	Schuri	ſ 		
X	·						Qа	te	X
Siegsdorf	State		c	ountry	Germany		Citize	nship	German
Bergstrasse 31									
						p11020 g 1900 man	,		
Siegsdorf	State			ZIP	83313	Count	ry	Gem	ıan
nal Joint Inventor, if any	/:			A petitic	on ha⊹ _⁄h iile	d for this	s unsig	ned in	ventor
me (first and middle [if any]	)				Family Nor	ne or Si	umame		
Tilmann					W	agner			
$\times$			Date +					+	
Grafing	State		Country Germany			Citizenship		German	
Am Seeschneidfel	d l								
Grafing	State			ŽIP	85567	Co	untry	Ge	rmany
	Matthias  Matthias  Grafing  Dietrich Bonhooffe  Grafing  Dietrich Bonhooffe  Grafing  Markus  Siegsdorf  Bergstrasse 31  Siegsdorf  al Joint Inventor, if any  Tilmann  Grafing  Am Secschneidfel	Grafing  Grafing  State  Dietrich Bonhocffer Stra  Grafing  State  Grafing  State  Markus  Siegsdorf  Bergstrasse 31  Siegsdorf  State  Bergstrasse 31  Siegsdorf  State  Grafing  Grafing  State  Am Seeschneidfeld 1	Matthias  DEK  Dietrich Bonhoeffer Strasse 4  Grafing  State  Mal Joint Inventor, if any:  Markus  Siegsdorf  Bergstrasse 31  Siegsdorf  State  Matthias  Matthias  State  Matthias  Matthias  Matthias  State  Matthias  Matthias	Matthias  Grafing  Dietrich Bonhoeffer Strasse 4  Grafing  State  DEK  Grafing  Dietrich Bonhoeffer Strasse 4  Grafing  State  Markus  Siegsdorf  Bergstrasse 31  Siegsdorf  State  Markus  Tilmann  Grafing  State  Grafing  Grafing  State  Grafing  State  Grafing  State  Grafing  State  Grafing  Grafing  State  Grafing	Matthias  Grafing  State  DEK Country  Dietrich Bonhocffer Strassc 4  Grafing  State  Tall Joint Inventor, if any:  Markus  Siegsdorf  State  Siegsdorf  State  Siegsdorf  State  Country  Bergstrasse 31  Siegsdorf  Tall Joint Inventor, if any:  A petition of the petition	Matthias  Grafing  State  DEK  Country  Germany  Dietrich Bonhoeffer Strasse 4  Grafing  State  Jap 85567  A petition has:  Siegsdorf  State  Siegsdorf  State  Siegsdorf  State  Siegsdorf  State  Siegsdorf  State  Country  Germany  A petition has:  A petition has:  Tamily Name (first and middle [if any])  Tilmann  W  Grafing  State  Country  Germany  Germany  A petition has:  Grafing  Grafing  State  Country  Germany  A petition has:  Grafing  Grafing  State  Grafing	Matthias   Knulle   K	Matthias   Examine or Surname   Matthias   Exhibit   Date	Matthias   Family Name or Sumane   Matthias   Country   Germany   Citizenship    Grafing   State   DEK   Country   Germany   Citizenship    Dietrich Bonhoeffer Strasse 4  Grafing   State   Zip   85567   Germany    Markus   A pelition has   As unsigned in the country    Markus   Schurf    Siegsdorf   State   Country   Germany   Citizenship    Bergstrasse 31  Siegsdorf   State   Zip   83313   Country   Germany    Markus   Country   Germany   Citizenship    Siegsdorf   State   Zip   83313   Country   Germany    Markus   Country   Germany   Citizenship    Markus   Country   Country   Country    Markus   Country   Country   Country    Markus   Country   Country   Country    Markus   Country   Country   Country    Markus   Cou

Burden Hour Statement: This form is estimated to take 0.4 hours to complete. Time will vary depending upon the needs of the individual case. Any comments on the amount of time, you are required to complete this form should be sent to the Chief Information Officer, Patent and Trademark Office, Washington, DC 20231. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: Assistant Commissioner for Patents, Washington, DC 20231.

Please type a plus sign (+) inside this box ->	+	
--	---	--

PTO/SB/02A (3-97)

Approved for use through 9/30/98, OMB 0651-0032

Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it contains a valid OMB control number valid OMB control number.

#### ADDITIONAL INVENTOR(S) **DECLARATION** Supplemental Sheet Name of Additional Joint Inventor, if any: A petition has ... this unslaned inventor Given Name (first and middle [if any]) Family Name or Sumame Knulle Matthias Inventor's Signature Date German Grafing Germany Residence: City Citizenship Countr Dietrich Bonhoeffer Strasse 4 Post Office Address Post Office Address 85567 Germany Grafing City State ZIP Name of Additional Joint Inventor, if any: A petition has la as unsigned inventor Given Name (first and middle [if any]) Tymily Name or Surname Schurf Markus Inventor's *X*2002 Signature Date Siegsdorf DEX Germany German Citizenship Residence: City Bergstrasse 31 Post Office Address Post Office Address Siegsdorf 83313 German City State ZIP Country Name of Additional Joint Inventor, if any: A petition has in Red for this unsigned inventor Given Name (first and middle [if any]) Family Name or Surname Tilmann Wagner Inventor's Signature Date Grafing Germany Citizenship German Residence: City State Country Am Seeschneidfeld 1 Post Office Address Post Office Address Grafing 85567 Germany Country פול State

Burden Hour Statement: This form is estimated to take 0.4 hours to complete. Time will vary depending upon the needs of the individual case. Any comments on the amount of time, you are required to complete this form should be sent to the Chief Information Officer, Patent and Trademark Officer, Washington, DC 20231. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: Assistant Commissioner for Patents, Washington, DC 20231.

H-W

Please type a p	lius sign (+) inside this box → +
	Under the Paperwork Reduction Act of valid OMB control number.
	DECLARATION

PTO/SB/02A (3-97)

Approved for use through 9/30/98, OMB 0551-0032

Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE on Act of 1995, no persons are required to respond to a collection of information unless it contains a

ADDITIONAL INVENTOR(S)
Supplemental Sheet

Name of Addition	nal Joint Inventor, if an	y:		A petitl	on has	√ thi	s unsign	ed in	ventor
Given Na	ome (first and middle [if any	1)			Family Na	ille or \$1	umame		
•	Matthias				K	Cnulle			
Inventor's Signature						Date	>	<u>۲</u>	
Residence: City	Grafing State			Country	Germany	/	Citizenship		
Post Office Address	Dietrich Bonhocfi	er Stra	15SC 4						
Post Office Address									
City	Grafing	State		ZiP	85567		Ger	man	y
Name of Additio	nat Joint Inventor, if an	y:	•	A petit	ion has 👉	4	s unsign	ed in	ventor
Given Na	ame (first and middle [if any	])	···	Tamily Name or Surname					
	Markus			Schurf					
Inventor's Signature	X						Dat	e	X
Residence: City	Siegsdorf	State		Country	Germany	,	Citizen	ship	Germa
Post Office Address	Bergstrasse 31					_ •			
Post Office Address									
City	Siegsdorf	State		ZIP	83313	Count	ry C	Gern	ıan
Name of Additio	nal Joint Inventor, if an	y:		A petit	ion har 🦽 🦚 🕮	ed for thi	s unsign	ned in	ventor
Given Na	ame (first and middle [if any	])			Family Na	me or S	umame		
	Tilmann			Wagner					
Inventor's Signature	× Te w	1					Dat	.0	X41/26
Residence: City	Grafing	State	DEX	Country	Germany		Citizen	ship	German
Post Office Address	Am Seeschneidfe	ld l							
Post Office Address									
City	Grafing	Sinia		פול	85567		untry	Gε	rmany

Burden Hour Statement: This form is estimated to take 0.4 hours to complete. Time will vary depending upon the needs of the individual case. Any comments on the amount of time, you are required to complete this form should be sent to the Chief Information Officer, Patent and Trademark Office, Washington, DC 20231. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: Assistant Commissioner for Patents, Washington, DC 20231.